



Q & A

Design & Construction of Amphitheater Stage Cover RFP

Updated 01.17.25

1. Can we provide electrical access on the shelter with cutouts but not lighting?

Yes, if your company does not provide lighting installation, you may include cutouts for electrical access on the shelter. Please note this on the proposal.

2. Can I visit the site to take measurements, etc.?

Yes, the site is open to the public and available to visit at any time. It is located directly behind the Mauldin Cultural Center building. 101 East Butler Drive, Mauldin, SC 29662

3. What is the amount of weight for speakers and lighting and where do the point loads need to be concentrated or located?

At minimum, point loads should be located at the front and rear of the stage to support temporary install of speakers/stage lights for events. The point loads should be able to hold a minimum of 1000 pounds each.

4. With the new footers/support beams being installed on the perimeter of the stage, do we need to include expansion of the sidewalk in our quote?

No, expanding the sidewalk is not a part of this project. However, you may list it as an optional add-on in your proposal.

5. The new footers/support beams will interfere with the landscaping behind the stage. Will the current landscaping be removed or is that a part of the contractor duties?

The current landscaping will be removed by our team prior to installation/construction beginning. This will be coordinated once the schedule is finalized with the winning bidder.

6. Do we need to include stonework for the new columns/support beams?

No, stonework is not a required part of this project. However, you may list it as an optional add-on in your proposal.

7. Is there an existing electrical panel?

Yes, there is an existing electrical panel on the backside of the stage (200A). It's measures approximately 14.25"x39" and is currently attached to a wooden structure. See photo below:

